# BRUHATH BENGALURU MAHANAGARA PALIKE

## Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No: EE/YNK/BBMP/E-PMT/18/2017-18 Dated: 31-01-2018

## APPROVED TENDER SCHEDULE –'B'

Item No: 02

Name of Work:-Drilling of borewell and providing pipe line in Yelahanka old town areas in ward no:02 of Yelahanka sub division

| Sl | Description | Unit | Approved Qty | Rate Quoted by the Contractor Approved Rates Sri SHADAYAN | |
|---|---|---|---|---|---|
| | | | | Rate | Rate in Words |
| 1 | KSRB 2-2.1 : Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No, KBS 2.1(a) / 2.3.5, No. 5/ Item No. 2.3 ) | Cum | 769.50 | 189.00 | Rupees One Hundred Eighty Nine Only |
| 2 | Providing and fixing Chorinated poly Venyl Chloride (CPVC) pipe conforming to IS 15778 having thermal stablity for hot and cold water supply including all CPVC plain and brass threaded fittings, this includesjointing of pipes and fittings with one step CPVC solvent cement trenching, refilling & testing of joints complete (external work) page No:97, item no 13.87.7 -do- 62.50mm nominal pipes OD pipes | Rmre | 1710.00 | 1410.00 | Rupees One Thousand Four Hundred Ten Only |
| 3 | KSRRB M400- Wet Mix Macadam - KSRRB M400-17. Providing, laying, spreading and compacting graded stones aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification No. 406 (P.No.158 I.No.20.18) | Cum | 153.90 | 1620.00 | Rupees One Thousand Six Hundred Twenty Only |
| 4 | Refilling available earth around pipelines, cables in layers not exceeding 20cms in depth compacting each deposited layers by ramming after watering lead upto 50m and lift upto 1.5m including cost of labour complete as per specification (P.No.6 I.No.2.11) | Cum | 769.50 | 60.00 | Rupees Sixty Only |

| | Description | Unit | Approved Qty | Rate Quoted by the Contractor Approved Rates Sri SHADAYAN | |
|---|---|---|---|---|---|
| | | | | Rate | Rate in Words |
| 5 | KSRB 13.6.3-6 : Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 50mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No. KBS 13.2.6/13.3 P. 92 / I.13.37 PWD SR 2016-17 | Each | 13.00 | 2130.00 | Rupees Two Thousand One Hundred Thirty Only |

SHADAYAN

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.